



JUNE 20, 2018

**Re: 18ITB050418-DRR, REMOVAL/INSTALLATION OF EXISTING
PLAYGROUND EQUIPMENT**

Dear Respondent(s):

Attached is one (1) copy of Addendum 1, hereby made a part of the above referenced 18ITB050418-DRR, Removal/Installation of Existing Playground Equipment.

Except as provided herein, all terms and conditions in the 18ITB050418-DRR referenced above remain unchanged and in full force and effect.

Sincerely,

Donald R. Riley

**Donald R. Riley, CPPB
Purchasing Specialist**

**18ITB050418-DRR, REMOVAL/INSTALLATION OF EXISTING PLAYGROUND
EQUIPMENT
Addendum No. 1
Page Two**

This Addendum forms a part of the contract documents and **modifies** the original ITB documents as noted below:

Attached hereto are responses to questions submitted in reference to the above quotation document.

Except as provided herein, all terms and conditions in the bid referenced above remain unchanged and in full force and effect.

Failure to return a signed copy of this addendum could render your bid non-responsive.

ACKNOWLEDGEMENT OF ADDENDUM NO. 1

The undersigned bidder acknowledges receipt of this addendum by returning one (1) copy of this form with the proposal package to the Finance Department - Purchasing Division, City of Stockbridge, 4640 Henry Boulevard, Stockbridge, Georgia 30281 by the quote due date and time **JUNE 27, 2018 before 12:00 P.M. (NOON) E.S.T.**

This is to acknowledge receipt of Addendum No. 1, _____ day of _____, 2018.

Legal Name of Bidder

Signature of Authorized Representative

Title

QUESTIONS REGARDING 17ITB012417-DRR, CLARK COMMUNITY PARK PLAYGROUND EQUIPMENT:

- 1) At Memorial Park, we will be able to install the EPDM PIP without removing the equipment. Is this acceptable?

Response: Yes. It is acceptable so long as the installer will grant a warranty for any seams or any repairs that may be needed to the EPDM.

- 2) At Memorial Park, will the swings need to be relocated and if so, will they remain in the same footprint as the Miracle structure?

Response: Yes. The swings will need to be relocated and remain in the same footprint as the current Miracle structure.

- 3) At Memorial Park, the square footage is stated as 4,446; does this amount cover the area where the swings are to be relocated too?

Response: The current playground area is approximately 75' x 35'. The area will need to be large enough to accommodate all the equipment being moved as well as the swings and have enough space, so the equipment is spaced apart per code.

- 4) The "aromatic" binder is not necessary for the colors of Green and Black. Is it acceptable to use the standard binder?

Response: Please quote both "aromatic" and "standard" binder prices on a separate sheet of paper.

- 5) At Gardner Park, will the swings need to be relocated as well because it's stated as equipment where the swings are mentioned specifically at Memorial Park.

Response: The area will need to be large enough to accommodate all the equipment being moved as well as the swings and have enough space, so the equipment is spaced apart per code.

- 6) At Gardner Park, once the equipment is relocated, do the timbers and mulch need to be disposed of where the Miracle equipment originally sat or is the city doing this?

Response: Please present a quote for disposal and without disposal on a separate sheet of paper.

- 7) At Gardner Park, the bid states that we are to remove the 2-5 equipment but at the site review, you stated that the city will remove the equipment and footers where the Miracle structure will be relocated too. Please confirm which one.

Response: Please present a quote for removal and non-removal on a separate sheet of paper.

- 8) At Gardner Park, are you wanting the two benches “replaced”?

Response: Please present a quote to replace both benches and no benches on a separate sheet of paper.